

RESULTS

PROJECT #: ADU2-NORTH. 0 || CSA F280



These results have been generated by The TECA Heat Loss & Heat Gain Calculator (V5.08), which is CSA F280 Verified

With the permission of Canadian Standards Association, (operating as "CSA Group"), 178 Rexdale Blvd., Toronto, ON, M9W 1R3, material is reproduced from CSA Group's standard CSA-F280-12 (R2017) Determining the required capacity of residential space heating and cooling appliances. This material is not the complete and official position of CSA Group on the referenced subject, which is represented solely by the Standard in its entirety. While use of the material has been authorized, CSA Group is not responsible for the manner in which the data is presented, nor for any representations and interpretations. No further reproduction is permitted. For more information or to purchase standard(s) from CSA Group, please visit store.csagroup.org or call 1-800-463-6727.

The heating and cooling loads calculated with this calculator tool are the sole responsibility of the user. This tool is to aid the user in applying to the CSA F280-12 calculation methods. The Thermal Environmental Comfort Association of BC accepts no responsibility for damages whatsoever, and offers no guarantee of equipment sizing or configuration.

BUILDING INFORMATION

CALCULATIONS PERFORMED FOR: BC MINISTRY OF HOUSING

CALCULATIONS PERFORMED BY

NAME TODD BACKUS
COMPANY TECA
ADDRESS PO BOX 73105, EVERGREEN RO
CITY SURREY
PROVINCE BC
POSTAL CODE V3R 0J2
PHONE 604-594-5956
FAX -
EMAIL TBACKUS@TECA.CA

SOFTWARE LICENSING

COMPANY
NAME
REG. #:



PROJECT #: ADU2-NORTH
ADDRESS:
CITY: PRINCE RUPERT
PROVINCE: BC
POSTAL CODE:
BUILDING MODEL: ADU-02
SITE: NORTH
LOT:



DESIGNER OF BUILDING DRAWINGS: Leckie Studio Architecture + Design Inc.

DATE OF DRAWINGS: September 6, 2024

BUILDING ATTACHMENT: Detached

NUMBER OF FLOOR LEVELS: 2 **NUMBER OF STOREYS:** 1 *above grade floor levels*

WEATHER DATA	Prince Rupert		
LATITUDE:	54.32	LONGITUDE:	-130.32
Summer Mean Daily Temperature Range	6 °C	WINDOW SHADING:	NO
VENTILATION SYSTEM	Non-dedicated HRV, 30CFM, ASE0.65, ATRE:0		
HEATING SYSTEM	forced air (central system with ductwork)		

FRONT OF HOUSE FACING DIRECTION:	W
<i>is this value assumed?</i>	yes

AIR TIGHTNESS / INFILTRATION	ACH50: 1.5, ELA: 172.2 cm ² , ELA @10Pa
<i>is the air tightness value assumed?</i>	yes

BUILDING SITE SHIELDING:	Low crops, x/H > 20
---------------------------------	---------------------

LOCAL WALL SHIELDING:	Light local shielding
------------------------------	-----------------------

LOCAL FLUE SHIELDING:	Light local shielding
------------------------------	-----------------------

INDOOR DESIGN TEMPERATURES:	# OF BEDROOMS:	1
------------------------------------	-----------------------	---

HEATING: 22°C, 71.6°F	# OF PEOPLE:	2
------------------------------	---------------------	---

COOLING: 24°C, 75.2°F		
------------------------------	--	--

OUTDOOR DESIGN TEMPERATURES:		
-------------------------------------	--	--

HEATING: -13°C, 8.6°F		
------------------------------	--	--

COOLING: 19°C, 66.2°F		
------------------------------	--	--

SOIL TEMPERATURE: 10 °C		
--------------------------------	--	--

Attached documents: _____

Assumptions noted (in addition to listed assumptions on page 1): _____

Notes from the calculator operator: _____

BUILDING ENVELOPE ELEMENTS

WALLS

1/ (TYP. EXT. WALL: R-22), inside wall, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 16"OC, R20 (5.5"), // Sheathing materials, Softwood plywood, // Insulation, Mineral wool and glass fibre, // Cladding materials, Vinyl siding, outside air; 22.42R-VALUE

CEILINGS

1/ (TYP. ROOF: R-32), inside ceilings, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 24"OC, custom insulation, // Sheathing materials, Softwood plywood, // Roofing materials, Built-up roofing, outside air; 32.01R-VALUE

INTERIOR FOUNDATION WALL

EXPOSED FLOOR

EXPOSED HEADER

1/ (TYP. HEADER: R-22); 22R-VALUE

WINDOWS

1/ (Windows (energy modeling assumptions)) custom, USI: 1.3, SHGC: 0.25

SKYLIGHTS

1/ (SKYLIGHT) double glazed, Fixed — Wood/Vinyl, insulating, low-E, 13mm Air, USI: 1.96, SHGC: 0.47

DOORS

1/ (EXT. DOOR) Insulated metal — Polyurethane core, without storm door, USI: 0.91

SHADINGS

FOUNDATIONS

1/ [Heated Crawlspace] Concrete Slab & Walls, insulation: below slab = 2.64RSI, interior wall = 2.11RSI, exterior wall = 2.11RSI (configuration #69) // any first storey construction type, interior surface of wall insulated over full-height, exterior surface of wall insulated over full-height, sub-surface of floor slab fully insulated but no insulation under footings, thermal-break between walls and floor slab // AREA: 680ft², FULL PERIMETER: 113ft, EXPOSED PERIMETER: 113ft

HEAT LOSS & HEAT GAIN SUMMARY, (BTUH)

imperial

▼

ROOM NAME	FLOOR LEVEL	FL AREA (ft²)	HEAT LOSS	HEAT GAIN	
			TOTAL	SENS.	TOTAL (sensible + latent)
(#1)HEATED CRAWL	1	678	3088		
(#2)100-ENTRY	2	67	521	32	42
(#3)101-LIVING	2	97	1336	2109	2742
(#4)102-KITCHEN/DINING	2	178	2136	2641	3434
(#5)103-BEDROOM	2	190	1331	147	191
(#6)104-WASHROOM	2	97	991	264	343
AREA			HEAT LOSS	GAIN (sens.)	GAIN (total)
OVERALL BUILDING			1307	9402	5193 6752

HEAT LOSS COMPONENT BREAKDOWN, (BTUH)											
ROOM NAME	WALL	CEILING	FLOOR	WINDOW & SKYLIGHT	DOOR & HATCH	FOUNDATION	LEAKAGE	VENTILATION	DISTRIBUTION	ADDITIONAL	TOTAL
(#1)HEATED CRAWL	433					1571	658	426			3088
(#2)100-ENTRY	47	132			282		36	23			521
(#3)101-LIVING	451	191		541			93	60			1336
(#4)102-KITCHEN/DINING	414	350		180	946		148	96			2136
(#5)103-BEDROOM	624	374		180			93	60			1331
(#6)104-WASHROOM	506	191		180			69	45			991
TOTAL BUILDING	<u>WAL.</u>	<u>CEI.</u>	<u>FLR.</u>	<u>WIN.</u>	<u>DR.</u>	<u>FND.</u>	<u>LEAK.</u>	<u>VENT.</u>	<u>DIST.</u>	<u>ADD.</u>	<u>TOTAL</u>
	2476	1238		1082	1229	1571	1097	710			9402

HEAT GAIN COMPONENT BREAKDOWN, (BTUH)

MINIMUM INSTALLED OUTPUT CAPACITY:

5401

MECHANICAL SYSTEM SIZING

HEATING

- The heating system capacity must meet or exceed 100% of the total building heat loss (the minimum installed system capacity equals the total heat loss for the building)
- The combined capacity of the heating distribution system must meet or exceed 100% of the heat loss of the room or space that it serves.

COOLING

- The installed system cooling capacity must meet or exceed 80% of the nominal cooling system capacity *(reflected in the MINIMUM INSTALLED CAPACITY shown for cooling)*.
- The installed system cooling capacity shall not be less than the nominal system cooling capacity minus 1800W *(reflected in the MINIMUM INSTALLED CAPACITY shown for cooling)*.
- If the cooling system is added to an existing heating system, its capacity (in Watts) need not exceed 18 times the air-handling capacity of the heating system (in L/s).
- Except for ground or water source heat pumps used for cooling, the installed cooling system capacity shall not exceed 125% of the nominal cooling system capacity for the building.
- If the nominal cooling system capacity for the building is less than 6000 W, the installed cooling system capacity may exceed the nominal cooling system capacity by up to 1750 W.
- Note that the nominal cooling system capacity incorporates a latent load multiplier value of 1.3 (unless specified otherwise). Most residential cooling units have a latent capacity of approximately 30% of the sensible capacity. For houses with very small latent loads (if the humidity values are entered by the user directly), it is important to mind the calculation factors. Equipment sizing must be done with individual consideration of sensible and latent loads.