

RESULTS

PROJECT #: DPLX2-U1-WEST. 0 || CSA F280



These results have been generated by The TECA Heat Loss & Heat Gain Calculator (V5.08), which is CSA F280 Verified

With the permission of Canadian Standards Association, (operating as "CSA Group"), 178 Rexdale Blvd., Toronto, ON, M9W 1R3, material is reproduced from CSA Group's standard CSA-F280-12 (R2017) Determining the required capacity of residential space heating and cooling appliances. This material is not the complete and official position of CSA Group on the referenced subject, which is represented solely by the Standard in its entirety. While use of the material has been authorized, CSA Group is not responsible for the manner in which the data is presented, nor for any representations and interpretations. No further reproduction is permitted. For more information or to purchase standard(s) from CSA Group, please visit store.csagroup.org or call 1-800-463-6727.

The heating and cooling loads calculated with this calculator tool are the sole responsibility of the user. This tool is to aid the user in applying to the CSA F280-12 calculation methods. The Thermal Environmental Comfort Association of BC accepts no responsibility for damages whatsoever, and offers no guarantee of equipment sizing or configuration.

BUILDING INFORMATION

CALCULATIONS PERFORMED FOR: BC MINISTRY OF HOUSING

CALCULATIONS PERFORMED BY

NAME TODD BACKUS
COMPANY TECA
ADDRESS PO BOX 73105, EVERGREEN RO
CITY SURREY
PROVINCE BC
POSTAL CODE V3R 0J2
PHONE 604-594-5956
FAX -
EMAIL TBACKUS@TECA.CA

SOFTWARE LICENSING

COMPANY
NAME
REG. #:



PROJECT #: DPLX2-U1-WEST
ADDRESS:
CITY: KELOWNA
PROVINCE: BC
POSTAL CODE:
BUILDING MODEL: DPLX-02-UNIT 1
SITE: WEST
LOT:



DESIGNER OF BUILDING DRAWINGS: Leckie Studio Architecture + Design Inc.
DATE OF DRAWINGS: September 6, 2024
BUILDING ATTACHMENT: Semi-Detached (Duplex)
NUMBER OF FLOOR LEVELS: 4 NUMBER OF STOREYS: 3 above grade floor levels

WEATHER DATA	Kelowna		
LATITUDE:	49.88	LONGITUDE:	-119.48
Summer Mean Daily Temperature Range	15 °C	WINDOW SHADING:	NO
VENTILATION SYSTEM	Non-dedicated HRV, 60CFM, ASE0.65, ATRE:0		
HEATING SYSTEM	forced air (central system with ductwork)		

FRONT OF HOUSE FACING DIRECTION:	S
<i>is this value assumed?</i>	yes

AIR TIGHTNESS / INFILTRATION	ACH50: 1.5, ELA: 230.9 cm ² , ELA @10Pa
<i>is the air tightness value assumed?</i>	yes

BUILDING SITE SHIELDING:	Low crops, x/H > 20
---------------------------------	---------------------

LOCAL WALL SHIELDING:	Light local shielding
------------------------------	-----------------------

LOCAL FLUE SHIELDING:	Light local shielding
------------------------------	-----------------------

INDOOR DESIGN TEMPERATURES:	# OF BEDROOMS:	3
HEATING: 22°C, 71.6°F	# OF PEOPLE:	4
COOLING: 24°C, 75.2°F		

OUTDOOR DESIGN TEMPERATURES:	
HEATING: -17°C, 1.4°F	
COOLING: 33°C, 91.4°F	

SOIL TEMPERATURE: 11 °C

Attached documents: _____

Assumptions noted (in addition to listed assumptions on page 1): _____

Notes from the calculator operator: _____

BUILDING ENVELOPE ELEMENTS

WALLS

1/ (TYP. EXT. WALL: R-22), inside wall, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 16"OC, R20 (5.5"), // Sheathing materials, Softwood plywood, // Insulation, Mineral wool and glass fibre, // Cladding materials, Vinyl siding, outside air; 22.42R-VALUE

CEILINGS

1/ (TYP. ROOF: R-32), inside ceilings, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 24"OC, custom insulation, // Sheathing materials, Softwood plywood, // Roofing materials, Built-up roofing, outside air; 32.01R-VALUE

INTERIOR FOUNDATION WALL

EXPOSED FLOOR

EXPOSED HEADER

1/ (TYP. HEADER: R-22); 22R-VALUE

WINDOWS

1/ (Windows (Energy modelling requirements)) custom, USI: 1.3, SHGC: 0.25

SKYLIGHTS

1/ (SKYLIGHT) double glazed, Fixed — Wood/Vinyl, insulating, low-E, 13mm Air, USI: 1.96, SHGC: 0.47

DOORS

1/ (EXT. DOOR) Insulated metal — Polyurethane core, without storm door, USI: 0.91

SHADINGS

FOUNDATIONS

1/ [Heated Crawlspace] Concrete Slab & Walls, insulation: below slab = 2.64RSI, interior wall = 2.11RSI, exterior wall = 2.11RSI (configuration #69) // any first storey construction type, interior surface of wall insulated over full-height, exterior surface of wall insulated over full-height, sub-surface of floor slab fully insulated but no insulation under footings, thermal-break between walls and floor slab // AREA: 448ft², FULL PERIMETER: 93ft, EXPOSED PERIMETER: 67ft

HEAT LOSS & HEAT GAIN SUMMARY, (BTUH)

imperial

▼

ROOM NAME	FLOOR LEVEL	FL AREA (ft²)	HEAT LOSS	HEAT GAIN	
			TOTAL	SENS.	TOTAL (sensible + latent)
(#1)HEATED CRAWL - U1	1	448	3006	56	73
(#2)100-ENTRY	2	34	1375	742	965
(#3)101-POWDER	2	20	148	26	34
(#4)102-LIVING ROOM	2	97	707	2311	3005
(#5)103-KITCHEN/DINING	2	297	2582	3531	4590
(#6)200-BEDROOM 1	3	136	1539	732	952
(#7)201-BEDROOM 2	3	136	612	455	592
(#8)202-WASHROOM	3	40			
(#9)203-LANDING	3	124	1312	556	723
(#10)300-BEDROOM 3	4	136	1497	905	1177
(#11)301-STUDY	4	136	804	638	829
(#12)302-WASHROOM	4	40	99	57	74
(#13)303-LANDING	4	124	1464	1440	1872
		AREA	HEAT LOSS	GAIN (sens.)	GAIN (total)
OVERALL BUILDING		1768	15144	11449	14884

PROJECT #: DPLX2-U1-WEST. 0

**HEAT LOSS COMPONENT
BREAKDOWN, (BTUH)**

ROOM NAME	WALL	CEILING	FLOOR	WINDOW & SKYLIGHT	DOOR & HATCH	FOUNDATION	LEAKAGE	VENTILATION	DISTRIBUTION	ADDITIONAL	TOTAL
(#1)HEATED CRAWL - U1	285					966	1122	633			3006
(#2)100-ENTRY	247			437	315		241	136			1375
(#3)101-POWDER	107						26	15			148
(#4)102-LIVING ROOM	312			201			124	70			707
(#5)103-KITCHEN/DINING	871			1004			452	255			2582
(#6)200-BEDROOM 1	747			402			249	141			1539
(#7)201-BEDROOM 2	256			201			99	56			612
(#8)202-WASHROOM											
(#9)203-LANDING	779			201			213	120			1312
(#10)300-BEDROOM 3	627	298		402			109	61			1497
(#11)301-STUDY	213	298		201			58	33			804
(#12)302-WASHROOM		88					7	4			99
(#13)303-LANDING	664	256		378			106	60			1464
TOTAL BUILDING	WAL.	CEI.	FLR.	WIN.	DR.	FND.	LEAK.	VENT.	DIST.	ADD.	TOTAL
	5109	940		3426	315	966	2806	1583			15144

PROJECT #: DPLX2-U1-WEST. 0

**HEAT GAIN
COMPONENT
BREAKDOWN, (BTUH)**

ROOM NAME	WALL	CEILING	FLOOR	WINDOW & SKYLIGHT	DOOR & HATCH	LEAKAGE	VENTILATION	DISTRIBUTION & ADDITIONAL	INTERNAL	TOTAL SENSIBLE	TOTAL SENSIBLE + LATENT
	WAL.	CEI.	FLR.	WIN.	DR.	LEAK.	VENT.	DIST.	INT.	SENS.	TOTAL
(#1)HEATED CRAWL - U1	47					2	8			56	73
(#2)100-ENTRY	40			549	32	22	100			742	965
(#3)101-POWDER	22					1	3			26	34
(#4)102-LIVING ROOM	63			329		14	63		1843	2311	3005
(#5)103-KITCHEN/DINING	150			1262		50	227		1843	3531	4590
(#6)200-BEDROOM 1	107			505		22	98			732	952
(#7)201-BEDROOM 2	52			329		13	61			455	592
(#8)202-WASHROOM											
(#9)203-LANDING	136			329		16	75			556	723
(#10)300-BEDROOM 3	91	161		505		27	122			905	1177
(#11)301-STUDY	43	161		329		19	86			638	829
(#12)302-WASHROOM		47				2	8			57	74
(#13)303-LANDING	116	138		949		42	194			1440	1872
TOTAL BUILDING	WAL.	CEI.	FLR.	WIN.	DR.	LEAK.	VENT.	DIST.	INT.	SENS.	TOTAL
	867	509		5084	32	228	1044		3685	11449	14884

MINIMUM INSTALLED OUTPUT CAPACITY: 11907

MECHANICAL SYSTEM SIZING

HEATING

- The heating system capacity must meet or exceed 100% of the total building heat loss (the minimum installed system capacity equals the total heat loss for the building)
- The combined capacity of the heating distribution system must meet or exceed 100% of the heat loss of the room or space that it serves.

COOLING

- The installed system cooling capacity must meet or exceed 80% of the nominal cooling system capacity (*reflected in the MINIMUM INSTALLED CAPACITY shown for cooling*).
- The installed system cooling capacity shall not be less than the nominal system cooling capacity minus 1800W (*reflected in the MINIMUM INSTALLED CAPACITY shown for cooling*).
- If the cooling system is added to an existing heating system, its capacity (in Watts) need not exceed 18 times the air-handling capacity of the heating system (in L/s).
- Except for ground or water source heat pumps used for cooling, the installed cooling system capacity shall not exceed 125% of the nominal cooling system capacity for the building.
- If the nominal cooling system capacity for the building is less than 6000 W, the installed cooling system capacity may exceed the nominal cooling system capacity by up to 1750 W.
- Note that the nominal cooling system capacity incorporates a latent load multiplier value of 1.3 (unless specified otherwise). Most residential cooling units have a latent capacity of approximately 30% of the sensible capacity. For houses with very small latent loads (if the humidity values are entered by the user directly), it is important to mind the calculation factors. Equipment sizing must be done with individual consideration of sensible and latent loads.