

RESULTS

PROJECT #: DPLX3-U1-EAST. 0 || CSA F280



These results have been generated by The TECA Heat Loss & Heat Gain Calculator (V5.08), which is CSA F280 Verified

With the permission of Canadian Standards Association, (operating as "CSA Group"), 178 Rexdale Blvd., Toronto, ON, M9W 1R3, material is reproduced from CSA Group's standard CSA-F280-12 (R2017) Determining the required capacity of residential space heating and cooling appliances. This material is not the complete and official position of CSA Group on the referenced subject, which is represented solely by the Standard in its entirety. While use of the material has been authorized, CSA Group is not responsible for the manner in which the data is presented, nor for any representations and interpretations. No further reproduction is permitted. For more information or to purchase standard(s) from CSA Group, please visit store.csagroup.org or call 1-800-463-6727.

The heating and cooling loads calculated with this calculator tool are the sole responsibility of the user. This tool is to aid the user in applying to the CSA F280-12 calculation methods. The Thermal Environmental Comfort Association of BC accepts no responsibility for damages whatsoever, and offers no guarantee of equipment sizing or configuration.

BUILDING INFORMATION

CALCULATIONS PERFORMED FOR: BC MINISTRY OF HOUSING

CALCULATIONS PERFORMED BY

NAME	TODD BACKUS
COMPANY	TECA
ADDRESS	PO BOX 73105, EVERGREEN RO
CITY	SURREY
PROVINCE	BC
POSTAL CODE	V3R 0J2
PHONE	604-594-5956
FAX	-
EMAIL	TBACKUS@TECA.CA

SOFTWARE LICENSING

COMPANY
NAME
REG. #:



PROJECT #:	DPLX3-U1-EAST
ADDRESS:	
CITY:	KELOWNA
PROVINCE:	BC
POSTAL CODE:	
BUILDING MODEL:	DPLX-03-UNIT 1
SITE:	EAST
LOT:	



DESIGNER OF BUILDING DRAWINGS:	Leckie Studio Architecture + Design Inc.		
DATE OF DRAWINGS:	September 6, 2024		
BUILDING ATTACHMENT:	Semi-Detached (Duplex)		
NUMBER OF FLOOR LEVELS:	3	NUMBER OF STOREYS:	2 above grade floor levels

WEATHER DATA	Kelowna		
LATITUDE:	49.88	LONGITUDE:	-119.48
Summer Mean Daily Temperature Range	15 °C	WINDOW SHADING:	NO
VENTILATION SYSTEM	Non-dedicated HRV, 45CFM, ASE0.65, ATRE:0		
HEATING SYSTEM	forced air (central system with ductwork)		

FRONT OF HOUSE FACING DIRECTION: N
is this value assumed? yes

AIR TIGHTNESS / INFILTRATION ACH50: 1.5, ELA: 167.4 cm², ELA @10Pa
is the air tightness value assumed? yes

BUILDING SITE SHIELDING: Low crops, x/H > 20

LOCAL WALL SHIELDING: Light local shielding

LOCAL FLUE SHIELDING: Light local shielding

INDOOR DESIGN TEMPERATURES:	# OF BEDROOMS:	2
HEATING: 22°C, 71.6°F	# OF PEOPLE:	3
COOLING: 24°C, 75.2°F		

OUTDOOR DESIGN TEMPERATURES:
HEATING: -17°C, 1.4°F
COOLING: 33°C, 91.4°F

SOIL TEMPERATURE: 11 °C

Attached documents:

Assumptions noted (in addition to listed assumptions on page 1):

Notes from the calculator operator:

BUILDING ENVELOPE ELEMENTS

WALLS

1/ (TYP. EXT. WALL: R-22), inside wall, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 16"OC, R20 (5.5"), // Sheathing materials, Softwood plywood, // Insulation, Mineral wool and glass fibre, // Cladding materials, Vinyl siding, outside air; 22.42R-VALUE

CEILINGS

1/ (TYP. ROOF: R-32), inside ceilings, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 24"OC, custom insulation, // Sheathing materials, Softwood plywood, // Roofing materials, Built-up roofing, outside air; 32.01R-VALUE

INTERIOR FOUNDATION WALL

EXPOSED FLOOR

EXPOSED HEADER

1/ (TYP. HEADER: R-22); 22R-VALUE

WINDOWS

1/ (Windows (Energy modelling requirements)) custom, USI: 1.3, SHGC: 0.25

SKYLIGHTS

1/ (SKYLIGHT) double glazed, Fixed — Wood/Vinyl, insulating, low-E, 13mm Air, USI: 1.96, SHGC: 0.47

DOORS

1/ (EXT. DOOR) Insulated metal — Polyurethane core, without storm door, USI: 0.91

SHADINGS

FOUNDATIONS

1/ [Heated Crawlspace] Concrete Slab & Walls, insulation: below slab = 2.64RSI, interior wall = 2.11RSI, exterior wall = 2.11RSI (configuration #69) // any first storey construction type, interior surface of wall insulated over full-height, exterior surface of wall insulated over full-height, sub-surface of floor slab fully insulated but no insulation under footings, thermal-break between walls and floor slab // AREA: 448ft², FULL PERIMETER: 93ft, EXPOSED PERIMETER: 82ft

HEAT LOSS & HEAT GAIN SUMMARY, (BTUH)

imperial

▼

ROOM NAME	FLOOR LEVEL	FL AREA (ft²)	HEAT LOSS	HEAT GAIN	
			TOTAL	SENS.	TOTAL (sensible + latent)
(#1)HEATED CRAWL - U1	1	448	2914	57	75
(#2)100-ENTRY	2	34	1175	417	542
(#3)101-POWDER	2	20	126	26	33
(#4)102-LIVING ROOM	2	97	1327	2718	3534
(#5)103-KITCHEN/DINING	2	297	2878	3078	4002
(#6)200-BEDROOM 1	3	136	1688	979	1273
(#7)201-BEDROOM 2	3	136	1629	1259	1637
(#8)202-WASHROOM	3	40	99	56	72
(#9)203-LANDING	3	124	1267	1023	1330
		AREA	HEAT LOSS	GAIN (sens.)	GAIN (total)
OVERALL BUILDING		1332	13103	9613	12498

HEAT LOSS COMPONENT
BREAKDOWN, (BTUH)

HEAT LOSS COMPONENT BREAKDOWN, (BTUH)				WINDOW & SKYLIGHT	DOOR & HATCH	FOUNDATION			DISTRIBUTION	ADDITIONAL	
	WALL	CEILING	FLOOR				LEAKAGE	VENTILATION			
ROOM NAME	WAL.	CEI.	FLR.	WIN.	DR.	FND.	LEAK.	VENT.	DIST.	ADD.	TOTAL
(#1)HEATED CRAWL - U1	350					1185	786	593			2914
(#2)100-ENTRY	247			437	315		101	76			1175
(#3)101-POWDER	107						11	8			126
(#4)102-LIVING ROOM	525			603			114	86			1327
(#5)103-KITCHEN/DINING	894			1236	315		246	186			2878
(#6)200-BEDROOM 1	588	298		603			113	86			1688
(#7)201-BEDROOM 2	536	298		603			109	83			1629
(#8)202-WASHROOM		88					7	5			99
(#9)203-LANDING	685	256		177			85	64			1267
	<u>WAL.</u>	<u>CEI.</u>	<u>FLR.</u>	<u>WIN.</u>	<u>DR.</u>	<u>FND.</u>	<u>LEAK.</u>	<u>VENT.</u>	<u>DIST.</u>	<u>ADD.</u>	<u>TOTAL</u>
TOTAL BUILDING	3932	940		3657	629	1185	1572	1187			13103

PROJECT #: DPLX3-U1-EAST. 0

HEAT GAIN COMPONENT BREAKDOWN, (BTUH)	WALL	CEILING	FLOOR	WINDOW & SKYLIGHT	DOOR & HATCH	LEAKAGE	VENTILATION	DISTRIBUTION & ADDITIONAL	INTERNAL	TOTAL SENSIBLE	TOTAL SENSIBLE + LATENT
ROOM NAME	WAL.	CEI.	FLR.	WIN.	DR.	LEAK.	VENT.	DIST.	INT.	SENS.	TOTAL
(#1)HEATED CRAWL - U1	49					1	7			57	75
(#2)100-ENTRY	36			301	19	9	53			417	542
(#3)101-POWDER	22					1	3			26	33
(#4)102-LIVING ROOM	91			757		21	126		1723	2718	3534
(#5)103-KITCHEN/DINING	139			983	32	29	172		1723	3078	4002
(#6)200-BEDROOM 1	67	161		606		21	124			979	1273
(#7)201-BEDROOM 2	78	161		834		27	160			1259	1637
(#8)202-WASHROOM		47				1	7			56	72
(#9)203-LANDING	112	138		621		22	130			1023	1330
	<u>WAL.</u>	<u>CEI.</u>	<u>FLR.</u>	<u>WIN.</u>	<u>DR.</u>	<u>LEAK.</u>	<u>VENT.</u>	<u>DIST.</u>	<u>INT.</u>	<u>SENS.</u>	<u>TOTAL</u>
TOTAL BUILDING	593	509		4101	51	131	783		3446	9613	12498

MINIMUM INSTALLED OUTPUT CAPACITY: 9998

MECHANICAL SYSTEM SIZING

HEATING

- The heating system capacity must meet or exceed 100% of the total building heat loss (the minimum installed system capacity equals the total heat loss for the building)
- The combined capacity of the heating distribution system must meet or exceed 100% of the heat loss of the room or space that it serves.

COOLING

- The installed system cooling capacity must meet or exceed 80% of the nominal cooling system capacity (*reflected in the MINIMUM INSTALLED CAPACITY shown for cooling*).
- The installed system cooling capacity shall not be less than the nominal system cooling capacity minus 1800W (*reflected in the MINIMUM INSTALLED CAPACITY shown for cooling*).
- If the cooling system is added to an existing heating system, its capacity (in Watts) need not exceed 18 times the air-handling capacity of the heating system (in L/s).
- Except for ground or water source heat pumps used for cooling, the installed cooling system capacity shall not exceed 125% of the nominal cooling system capacity for the building.
- If the nominal cooling system capacity for the building is less than 6000 W, the installed cooling system capacity may exceed the nominal cooling system capacity by up to 1750 W.
- Note that the nominal cooling system capacity incorporates a latent load multiplier value of 1.3 (unless specified otherwise). Most residential cooling units have a latent capacity of approximately 30% of the sensible capacity. For houses with very small latent loads (if the humidity values are entered by the user directly), it is important to mind the calculation factors. Equipment sizing must be done with individual consideration of sensible and latent loads.