

RESULTS

PROJECT #: QPLX1-U3-EAST. 0 || CSA F280



These results have been generated by The TECA Heat Loss & Heat Gain Calculator (V5.08), which is CSA F280 Verified

With the permission of Canadian Standards Association, (operating as "CSA Group"), 178 Rexdale Blvd., Toronto, ON, M9W 1R3, material is reproduced from CSA Group's standard CSA-F280-12 (R2017) Determining the required capacity of residential space heating and cooling appliances. This material is not the complete and official position of CSA Group on the referenced subject, which is represented solely by the Standard in its entirety. While use of the material has been authorized, CSA Group is not responsible for the manner in which the data is presented, nor for any representations and interpretations. No further reproduction is permitted. For more information or to purchase standard(s) from CSA Group, please visit store.csagroup.org or call 1-800-463-6727.

The heating and cooling loads calculated with this calculator tool are the sole responsibility of the user. This tool is to aid the user in applying to the CSA F280-12 calculation methods. The Thermal Environmental Comfort Association of BC accepts no responsibility for damages whatsoever, and offers no guarantee of equipment sizing or configuration.

BUILDING INFORMATION

CALCULATIONS PERFORMED FOR: BC MINISTRY OF HOUSING

CALCULATIONS PERFORMED BY

NAME	TODD BACKUS
COMPANY	TECA
ADDRESS	PO BOX 73105, EVERGREEN RO
CITY	SURREY
PROVINCE	BC
POSTAL CODE	V3R 0J2
PHONE	604-594-5956
FAX	-
EMAIL	TBACKUS@TECA.CA

SOFTWARE LICENSING

COMPANY
NAME
REG. #:



PROJECT #:	QPLX1-U3-EAST
ADDRESS:	
CITY:	KELOWNA
PROVINCE:	BC
POSTAL CODE:	
BUILDING MODEL:	QPLX-01-UNIT 3
SITE:	EAST
LOT:	



DESIGNER OF BUILDING DRAWINGS:	Leckie Studio Architecture + Design Inc.		
DATE OF DRAWINGS:	September 6, 2024		
BUILDING ATTACHMENT:	Row House - Middle Unit		
NUMBER OF FLOOR LEVELS:	4	NUMBER OF STOREYS:	3 above grade floor levels

WEATHER DATA	Kelowna		
LATITUDE:	49.88	LONGITUDE:	-119.48
Summer Mean Daily Temperature Range	15 °C	WINDOW SHADING:	NO
VENTILATION SYSTEM	Non-dedicated HRV, 60CFM, ASE0.65, ATRE:0		
HEATING SYSTEM	forced air (central system with ductwork)		

FRONT OF HOUSE FACING DIRECTION: E
is this value assumed? yes

AIR TIGHTNESS / INFILTRATION ACH50: 1.5, ELA: 158.8 cm², ELA @10Pa
is the air tightness value assumed? yes

BUILDING SITE SHIELDING: Low crops, x/H > 20

LOCAL WALL SHIELDING: Light local shielding

LOCAL FLUE SHIELDING: Light local shielding

INDOOR DESIGN TEMPERATURES: **# OF BEDROOMS:** 2

HEATING: 22°C, 71.6°F

OF PEOPLE: 3

COOLING: 24°C, 75.2°F

OUTDOOR DESIGN TEMPERATURES:

HEATING: -17°C, 1.4°F

COOLING: 33°C, 91.4°F

SOIL TEMPERATURE: 11 °C

Attached documents: _____

Assumptions noted (in addition to listed assumptions on page 1): _____

Notes from the calculator operator: _____

BUILDING ENVELOPE ELEMENTS

WALLS

1/ (TYP. EXT. WALL: R-22), inside wall, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 16"OC, R20 (5.5"), // Sheathing materials, Softwood plywood, // Insulation, Mineral wool and glass fibre, // Cladding materials, Vinyl siding, outside air; 22.42R-VALUE

CEILINGS

1/ (TYP. ROOF: R-32), inside ceilings, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 24"OC, custom insulation, // Sheathing materials, Softwood plywood, // Roofing materials, Built-up roofing, outside air; 32.01R-VALUE

INTERIOR FOUNDATION WALL

EXPOSED FLOOR

1/ (TYP. EXPOSED FLOOR), inside floor, // Finished floor w/ underlay, // 3/4" ply, // framing w/ cavity insulation: softwood (default), 2x12 joists @ 16"OC, R35 (9.25"), // Exterior finished material, // outside air; 30.98R-VALUE

EXPOSED HEADER

1/ (TYP. HEADER: R-22); 22R-VALUE

WINDOWS

1/ (Windows (Energy modelling requirements)) custom, USI: 1.3, SHGC: 0.25

SKYLIGHTS

1/ (SKYLIGHT) double glazed, Fixed — Wood/Vinyl, insulating, low-E, 13mm Air, USI: 1.96, SHGC: 0.47

DOORS

1/ (EXT. DOOR) Insulated metal — Polyurethane core, without storm door, USI: 0.91

SHADINGS

FOUNDATIONS

1/ [Heated Crawlspace] Concrete Slab & Walls, insulation: below slab = 2.64RSI, interior wall = 2.11RSI, exterior wall = 2.11RSI (configuration #69) // any first storey construction type, interior surface of wall insulated over full-height, exterior surface of wall insulated over full-height, sub-surface of floor slab fully insulated but no insulation under footings, thermal-break between walls and floor slab // AREA: 144ft², FULL PERIMETER: 56ft, EXPOSED PERIMETER: 56ft

HEAT LOSS & HEAT GAIN SUMMARY, (BTUH)

imperial



ROOM NAME	FLOOR LEVEL	FL AREA (ft²)	HEAT LOSS	HEAT GAIN	
			TOTAL	SENS.	TOTAL (sensible + latent)
(#1)HEATED CRAWL - U3	1	144	2221	22	29
(#2)104-ENTRY & STAIRS	2	166	4021	1792	2329
(#3)206-KITCHEN/DINING	3	292	2585	4187	5443
(#4)207-LIVING ROOM	3	113	1167	2914	3788
(#5)208-STUDY	3	46	766	372	484
(#6)308-LANDING	4	124	975	965	1255
(#7)309-WASHROOM	4	40	97	55	71
(#8)310-BEDROOM 1	4	136	1159	1026	1334
(#9)311-BEDROOM 2	4	136	1289	1043	1355
		AREA	HEAT LOSS	GAIN (sens.)	GAIN (total)
OVERALL BUILDING		1197	14279	12375	16088

HEAT LOSS COMPONENT
BREAKDOWN, (BTUH)

HEAT LOSS COMPONENT BREAKDOWN, (BTUH)				WINDOW & SKYLIGHT	DOOR & HATCH	FOUNDATION			DISTRIBUTION	ADDITIONAL	
	WALL	CEILING	FLOOR				LEAKAGE	VENTILATION			
ROOM NAME	WAL.	CEI.	FLR.	WIN.	DR.	FND.	LEAK.	VENT.	DIST.	ADD.	TOTAL
(#1)HEATED CRAWL - U3	94					721	772	633			2221
(#2)104-ENTRY & STAIRS	1251			771	944		579	475			4021
(#3)206-KITCHEN/DINING	810		168	1205			221	181			2585
(#4)207-LIVING ROOM	127		256	603			100	82			1167
(#5)208-STUDY	342		104	201			65	54			766
(#6)308-LANDING	445	256		177			53	44			975
(#7)309-WASHROOM		88					5	4			97
(#8)310-BEDROOM 1	343	298		402			64	52			1159
(#9)311-BEDROOM 2	460	298		402			71	58			1289
	WAL.	CEI.	FLR.	WIN.	DR.	FND.	LEAK.	VENT.	DIST.	ADD.	TOTAL
TOTAL BUILDING	3872	940	528	3761	944	721	1930	1583			14279

PROJECT #: QPLX1-U3-EAST. 0

**HEAT GAIN
COMPONENT
BREAKDOWN, (BTUH)**

ROOM NAME	WALL	CEILING	FLOOR	WINDOW & SKYLIGHT	DOOR & HATCH	LEAKAGE	VENTILATION	DISTRIBUTION & ADDITIONAL	INTERNAL	TOTAL SENSIBLE	TOTAL SENSIBLE + LATENT
	WAL.	CEI.	FLR.	WIN.	DR.	LEAK.	VENT.	DIST.	INT.	SENS.	TOTAL
(#1)HEATED CRAWL - U3	19					0	3			22	29
(#2)104-ENTRY & STAIRS	138			1262	151	31	209			1792	2329
(#3)206-KITCHEN/DINING	148		12	1972		43	288		1723	4187	5443
(#4)207-LIVING ROOM	26		19	986		21	139		1723	2914	3788
(#5)208-STUDY	62		8	252		7	43			372	484
(#6)308-LANDING	76	138		621		17	113			965	1255
(#7)309-WASHROOM		47				1	6			55	71
(#8)310-BEDROOM 1	70	161		657		18	120			1026	1334
(#9)311-BEDROOM 2	84	161		657		18	122			1043	1355
TOTAL BUILDING	WAL.	CEI.	FLR.	WIN.	DR.	LEAK.	VENT.	DIST.	INT.	SENS.	TOTAL
	622	509	39	6408	151	157	1044		3446	12375	16088

MINIMUM INSTALLED OUTPUT CAPACITY: 12871

MECHANICAL SYSTEM SIZING

HEATING

- The heating system capacity must meet or exceed 100% of the total building heat loss (the minimum installed system capacity equals the total heat loss for the building)
- The combined capacity of the heating distribution system must meet or exceed 100% of the heat loss of the room or space that it serves.

COOLING

- The installed system cooling capacity must meet or exceed 80% of the nominal cooling system capacity (*reflected in the MINIMUM INSTALLED CAPACITY shown for cooling*).
- The installed system cooling capacity shall not be less than the nominal system cooling capacity minus 1800W (*reflected in the MINIMUM INSTALLED CAPACITY shown for cooling*).
- If the cooling system is added to an existing heating system, its capacity (in Watts) need not exceed 18 times the air-handling capacity of the heating system (in L/s).
- Except for ground or water source heat pumps used for cooling, the installed cooling system capacity shall not exceed 125% of the nominal cooling system capacity for the building.
- If the nominal cooling system capacity for the building is less than 6000 W, the installed cooling system capacity may exceed the nominal cooling system capacity by up to 1750 W.
- Note that the nominal cooling system capacity incorporates a latent load multiplier value of 1.3 (unless specified otherwise). Most residential cooling units have a latent capacity of approximately 30% of the sensible capacity. For houses with very small latent loads (if the humidity values are entered by the user directly), it is important to mind the calculation factors. Equipment sizing must be done with individual consideration of sensible and latent loads.