

RESULTS

PROJECT #: QPLX2-U2-SOUTH. 0 || CSA F280



These results have been generated by The TECA Heat Loss & Heat Gain Calculator (V5.08), which is CSA F280 Verified

With the permission of Canadian Standards Association, (operating as "CSA Group"), 178 Rexdale Blvd., Toronto, ON, M9W 1R3, material is reproduced from CSA Group's standard CSA-F280-12 (R2017) Determining the required capacity of residential space heating and cooling appliances. This material is not the complete and official position of CSA Group on the referenced subject, which is represented solely by the Standard in its entirety. While use of the material has been authorized, CSA Group is not responsible for the manner in which the data is presented, nor for any representations and interpretations. No further reproduction is permitted. For more information or to purchase standard(s) from CSA Group, please visit store.csagroup.org or call 1-800-463-6727.

The heating and cooling loads calculated with this calculator tool are the sole responsibility of the user. This tool is to aid the user in applying to the CSA F280-12 calculation methods. The Thermal Environmental Comfort Association of BC accepts no responsibility for damages whatsoever, and offers no guarantee of equipment sizing or configuration.

BUILDING INFORMATION

CALCULATIONS PERFORMED FOR: BC MINISTRY OF HOUSING

CALCULATIONS PERFORMED BY

NAME TODD BACKUS
COMPANY TECA
ADDRESS PO BOX 73105, EVERGREEN RO
CITY SURREY
PROVINCE BC
POSTAL CODE V3R 0J2
PHONE 604-594-5956
FAX -
EMAIL TBACKUS@TECA.CA

SOFTWARE LICENSING

COMPANY
NAME
REG. #:



PROJECT #: QPLX2-U2-SOUTH
ADDRESS:
CITY: KELOWNA
PROVINCE: BC
POSTAL CODE:
BUILDING MODEL: QPLX-02-UNIT 2
SITE: SOUTH
LOT:



DESIGNER OF BUILDING DRAWINGS: Leckie Studio Architecture + Design Inc.
DATE OF DRAWINGS: September 6, 2024
BUILDING ATTACHMENT: Row House - Middle Unit
NUMBER OF FLOOR LEVELS: 4 **NUMBER OF STOREYS:** 3 *above grade floor levels*

WEATHER DATA	Kelowna		
LATITUDE:	49.88	LONGITUDE:	-119.48
Summer Mean Daily Temperature Range	15 °C	WINDOW SHADING:	NO
VENTILATION SYSTEM	Non-dedicated HRV, 60CFM, ASE0.65, ATRE:0		
HEATING SYSTEM	forced air (central system with ductwork)		

FRONT OF HOUSE FACING DIRECTION: E
is this value assumed? yes

AIR TIGHTNESS / INFILTRATION ACH50: 1.5, ELA: 230.4 cm², ELA @10Pa
is the air tightness value assumed? yes

BUILDING SITE SHIELDING: Low crops, x/H > 20

LOCAL WALL SHIELDING: Light local shielding

LOCAL FLUE SHIELDING: Light local shielding

INDOOR DESIGN TEMPERATURES: **# OF BEDROOMS:** 3

HEATING: 22°C, 71.6°F

OF PEOPLE: 4

COOLING: 24°C, 75.2°F

OUTDOOR DESIGN TEMPERATURES:

HEATING: -17°C, 1.4°F

COOLING: 33°C, 91.4°F

SOIL TEMPERATURE: 11 °C

Attached documents:

Assumptions noted (in addition to listed assumptions on page 1):

Notes from the calculator operator:

BUILDING ENVELOPE ELEMENTS

WALLS

1/ (TYP. EXT. WALL: R-22), inside wall, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 16"OC, R20 (5.5"), // Sheathing materials, Softwood plywood, // Insulation, Mineral wool and glass fibre, // Cladding materials, Vinyl siding, outside air; 22.42R-VALUE

CEILINGS

1/ (TYP. ROOF: R-32), inside ceilings, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 24"OC, custom insulation, // Sheathing materials, Softwood plywood, // Roofing materials, Built-up roofing, outside air; 32.01R-VALUE

INTERIOR FOUNDATION WALL

EXPOSED FLOOR

1/ (TYP. EXPOSED FLOOR), inside floor, // Finished floor w/ underlay, // 3/4" ply, // framing w/ cavity insulation: softwood (default), 2x12 joists @ 16"OC, R35 (9.25"), // Exterior finished material, // outside air; 30.98R-VALUE

EXPOSED HEADER

1/ (TYP. HEADER: R-22); 22R-VALUE

WINDOWS

1/ (Windows (Energy Modelling Requirements)) custom, USI: 1.3, SHGC: 0.25

SKYLIGHTS

1/ (SKYLIGHT) double glazed, Fixed — Wood/Vinyl, insulating, low-E, 13mm Air, USI: 1.96, SHGC: 0.47

DOORS

1/ (EXT. DOOR) Insulated metal — Polyurethane core, without storm door, USI: 0.91

SHADINGS

FOUNDATIONS

1/ [Heated Crawlspace] Concrete Slab & Walls, insulation: below slab = 2.64RSI, interior wall = 2.11RSI, exterior wall = 2.11RSI (configuration #69) // any first storey construction type, interior surface of wall insulated over full-height, exterior surface of wall insulated over full-height, sub-surface of floor slab fully insulated but no insulation under footings, thermal-break between walls and floor slab // AREA: 425ft², FULL PERIMETER: 91ft, EXPOSED PERIMETER: 71ft

HEAT LOSS & HEAT GAIN SUMMARY, (BTUH)

imperial

▼

ROOM NAME	FLOOR LEVEL	FL AREA (ft²)	HEAT LOSS	HEAT GAIN	
			TOTAL	SENS.	TOTAL (sensible + latent)
(#1)HEATED CRAWL - U2	1	425	3067	47	61
(#2)104-ENTRY	2	34	1342	933	1213
(#3)105-POWDER ROOM	2	20	144	13	17
(#4)106-LIVING ROOM	2	97	1509	3062	3981
(#5)107-KITCHEN/DINING	2	295	2202	3184	4140
(#6)204-BEDROOM 1	3	136	1609	1171	1522
(#7)205-BEDROOM 2	3	136	1401	884	1149
(#8)206-WASHROOM	3	40			
(#9)207-LANDING	3	124	924	195	254
(#10)300-STUDY	4	136	1646	1351	1756
(#11)301-BEDROOM 3	4	136	1468	1064	1383
(#12)302-WASHROOM	4	40	96	55	71
(#13)303-LANDING	4	124	1649	1158	1506
		AREA	HEAT LOSS	GAIN (sens.)	GAIN (total)
OVERALL BUILDING		1743	17058	13117	17053

PROJECT #: QPLX2-U2-SOUTH. 0

HEAT LOSS COMPONENT BREAKDOWN, (BTUH)											
ROOM NAME	WALL	CEILING	FLOOR	WINDOW & SKYLIGHT	DOOR & HATCH	FOUNDATION	LEAKAGE	VENTILATION	DISTRIBUTION	ADDITIONAL	TOTAL
(#1)HEATED CRAWL - U2	301					1014	1120	633			3067
(#2)104-ENTRY	255			432	315		217	123			1342
(#3)105-POWDER ROOM	107						23	13			144
(#4)106-LIVING ROOM	525			603			244	138			1509
(#5)107-KITCHEN/DINING	697			633	315		356	201			2202
(#6)204-BEDROOM 1	648			603			229	129			1609
(#7)205-BEDROOM 2	687			402			199	113			1401
(#8)206-WASHROOM											
(#9)207-LANDING	517			201			132	74			924
(#10)300-STUDY	596	298		603			95	54			1646
(#11)301-BEDROOM 3	636	298		402			85	48			1468
(#12)302-WASHROOM		88					6	3			96
(#13)303-LANDING	867	256		378			95	54			1649
	<u>WAL.</u>	<u>CEI.</u>	<u>FLR.</u>	<u>WIN.</u>	<u>DR.</u>	<u>FND.</u>	<u>LEAK.</u>	<u>VENT.</u>	<u>DIST.</u>	<u>ADD.</u>	<u>TOTAL</u>
TOTAL BUILDING	5836	940		4256	629	1014	2800	1583			17058

PROJECT #: QPLX2-U2-SOUTH. 0

HEAT GAIN COMPONENT BREAKDOWN, (BTUH)				WINDOW & SKYLIGHT	DOOR & HATCH			DISTRIBUTION & ADDITIONAL	INTERNAL	TOTAL SENSIBLE	TOTAL SENSIBLE + LATENT
	WALL	CEILING	FLOOR			LEAKAGE	VENTILATION				
ROOM NAME	WAL.	CEI.	FLR.	WIN.	DR.	LEAK.	VENT.	DIST.	INT.	SENS.	TOTAL
(#1)HEATED CRAWL - U2	40					1	5			47	61
(#2)104-ENTRY	36			707	64	23	103			933	1213
(#3)105-POWDER ROOM	11					0	1			13	17
(#4)106-LIVING ROOM	69			986		29	135		1843	3062	3981
(#5)107-KITCHEN/DINING	61			1036	64	32	148		1843	3184	4140
(#6)204-BEDROOM 1	103			910		28	130			1171	1522
(#7)205-BEDROOM 2	107			657		21	98			884	1149
(#8)206-WASHROOM											
(#9)207-LANDING	31			138		5	22			195	254
(#10)300-STUDY	98	161		910		33	149			1351	1756
(#11)301-BEDROOM 3	102	161		657		26	118			1064	1383
(#12)302-WASHROOM		47				1	6			55	71
(#13)303-LANDING	104	138		759		28	128			1158	1506
	<u>WAL.</u>	<u>CEI.</u>	<u>FLR.</u>	<u>WIN.</u>	<u>DR.</u>	<u>LEAK.</u>	<u>VENT.</u>	<u>DIST.</u>	<u>INT.</u>	<u>SENS.</u>	<u>TOTAL</u>
TOTAL BUILDING	763	509		6761	127	228	1044		3685	13117	17053

MINIMUM INSTALLED OUTPUT CAPACITY: 13642

MECHANICAL SYSTEM SIZING

HEATING

- The heating system capacity must meet or exceed 100% of the total building heat loss (the minimum installed system capacity equals the total heat loss for the building)
- The combined capacity of the heating distribution system must meet or exceed 100% of the heat loss of the room or space that it serves.

COOLING

- The installed system cooling capacity must meet or exceed 80% of the nominal cooling system capacity *(reflected in the MINIMUM INSTALLED CAPACITY shown for cooling)*.
- The installed system cooling capacity shall not be less than the nominal system cooling capacity minus 1800W *(reflected in the MINIMUM INSTALLED CAPACITY shown for cooling)*.
- If the cooling system is added to an existing heating system, its capacity (in Watts) need not exceed 18 times the air-handling capacity of the heating system (in L/s).
- Except for ground or water source heat pumps used for cooling, the installed cooling system capacity shall not exceed 125% of the nominal cooling system capacity for the building.
- If the nominal cooling system capacity for the building is less than 6000 W, the installed cooling system capacity may exceed the nominal cooling system capacity by up to 1750 W.
- Note that the nominal cooling system capacity incorporates a latent load multiplier value of 1.3 (unless specified otherwise). Most residential cooling units have a latent capacity of approximately 30% of the sensible capacity. For houses with very small latent loads (if the humidity values are entered by the user directly), it is important to mind the calculation factors. Equipment sizing must be done with individual consideration of sensible and latent loads.