

CSA STANDARD F280-12 COMPLIANCE				CSA F280-12 Form Set Ver 24.10	
NBC 2015: 9.33.5.1.; 9.36.3.2. & 9.36.5.15; NBC 2020; 9.33.5.1.; 9.36.3.2.; 9.36.5.15 (5); 9.36.8.9. (1);					
These documents issued for the use of BC MINISTRY OF HOUSING				PROJECT #	
and may not be used by any other persons without authorization. Documents for permit and/or construction are signed in red.				1 TOWN1-U4-SOUTH 2	
BUILDING LOCATION					
Model: TOWN-01-UNIT 4		3 Site: SOUTH		6	
Address:		4 Lot:		7	
City & Province: PRINCE GEORGE, BC		5 Postal Code:		8	
COMPLIANCE (See page 2 for input summary and page 3 for room by room values)					
Submittal is for: ☐ Whole house aw		☒ Room by Room ar		Units: ☒ Imperial ☐ Metric b	
HEATING					
Minimum Heating Capacity:		27,840		BTUH (total building heat loss as per 5.2.7) c	
5.3.1		The total heat output capacity of all heating systems installed in a building shall not be less than 100% of the total building heat loss as determined in Clause 5.2.7.			
5.3.2		The combined heating delivery of the heating systems that serve a room or space shall not be less than 100% of the space heat loss , as determined in Clause 5.2.6.. (If room by room submittal, see page 2 for individual space heating requirements)			
COOLING					
Nominal Cooling Capacity:		14,504		BTUH (Nominal Cooling Capacity as per 6.3.1) d	
Minimum Cooling Capacity:		11,603		BTUH e	
		Maximum Cooling Capacity:		18,130	
		BTUH f			
6.3.2		Except as provided in Clause 6.3.3., the cooling system capacity shall not be less than 80% of the nominal cooling capacity for the building, as determined in Clause 6.3.1.. In no case shall it be less than the nominal cooling capacity of the building minus 1800 W (0.51 tons)			
6.3.3		Where the cooling system is added to an existing heating system, it's capacity in Watts shall not exceed 18 times the capacity of the air-handling capacity of the existing system in L/s. (Cooling capacity in Tons not more than 1.0 per 400 CFM of air handling capacity)			
6.3.4		Except for ground-source and water source heat pumps used for cooling, and as permitted in Clause 6.3.5, the installed cooling capacity shall not exceed 125% of the nominal cooling capacity for the building, as determined in Clause 6.3.1.			
6.3.5		If the nominal cooling system capacity for the building, as determined in Clause 6.3.1. is less than 6,000 W (1.7 tons), the installed cooling system capacity may exceed the nominal cooling system capacity for the building by up to 1750 W (0.49 tons).			
ATTACHED DOCUMENTS					
☒ Design Summary g		☒ Room by Room Results h		Other: i	
Other: j					
Notes: j					
CALCULATIONS PERFORMED BY					
Name: TODD BACKUS 55		Designers Signature, Stamp Imprint or other certification mark		I, _____	
Company: TECA 56				have reviewed and take responsibility for the design	
Address: PO BOX 73105, EVERGREEN RO 57				work described in this document & I am qualified in the	
City & Prov.: SURREY, BC 58				appropriate categories. 63	
Postal Code: V3R 0J2 59				Accreditation Reference 1 64	
Phone: 604-594-5956 60				Accreditation Reference 2 65	
Fax: - 61				Issued for: 66	
E-mail: TBACKUS@TECA.CA 62				Issued for: 67	
		68 Page: 1 of 3			
		TECA HEAT LOSS & HEAT GAIN CALCULATOR		 HVAC DESIGNERS OF CANADA VERIFIED F280 SOFTWARE	

CSA F280-12 INPUT SUMMARY						CSA F280-12 Form Set Ver 24.10		
These documents issued for the use of <u>BC MINISTRY OF HOUSING</u>						1		
and may not be used by any other persons without authorization. Documents for permit and/or construction are signed in red.						2		
BUILDING LOCATION								
Model: TOWN-01-UNIT 4			3 Site: SOUTH		6 Lot:		7	
Address:			4 City/ Prov: PRINCE GEORGE, BC		5 Post. Code:		8	
CALCULATION BASED ON (See Following Page For Results)								
Dimensional Info Based On:			drawings done by: Leckie Studio Architecture + Design Inc.					
Attachment: Row House - End Unit			10 Front Facing: N		16 Assumed? Yes		17	
# of Stories: 3 (4 total floors)			11 Air Tightness: 1.5		18 Assumed? Yes		19	
Weather Location: Prince George			12 Internal Shading: No		21 Assumed? Yes		21a	
Wind Exposure, Site: Low crops, x/H > 20			20 Occupants: 5		22 Assumed? Yes		22a	
Wind Sheltering, Building: Light local shielding			20a Ventilated? Non-dedicated HRV		13 HRV/ERV? Yes		14	
Units: ☒ Imperial bi ☐ Metric bm			HRV ASE %: 65%		15 HRV ATRE %: 0%		15a	
HEATING DESIGN CONDITIONS				COOLING DESIGN CONDITIONS				
Outdoor Temp: -32°C, -25.6°F		24 Indoor Temp: 22°C, 71.6°F		25 Mean Soil Temp: 6°C, 42.8°F		26 Outdoor Temp: 28°C, 82.4°F		27 Range: 12°C, 53.6°F
Soil Cond. Normal conductivity: dry sand, loam, clay		26a Water Table Depth: Normal (7-10m, 23-33ft)		26b Slab Fluid Temp: None		28 Indoor Temp: 24°C, 75.2°F		30 Latitude: 53.92
ABOVE GRADE WALLS				BELOW GRADE WALLS				
ID 1: 1/ (TYP. EXT. WALL: R-22), inside wall, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 16"OC, R20 (5.5"), // Sheathing materials, Softwood plywood, // Insulation, Mineral wool and glass fibre, // Cladding materials, Vinyl siding, outside air; 22.42R-VALUE				ID 1:				31a 34a
FLOOR HEADERS				CEILINGS				
ID 1: 1/ (TYP. HEADER: R-22); 22R-VALUE				ID 1: 1/ (TYP. ROOF: R-32), inside ceilings, // 1/2" GWB, // framing w/ cavity insulation: softwood (default), 2x6 framing @ 24"OC, custom insulation, // Sheathing materials, Softwood plywood, // Roofing materials, Built-up roofing, outside air; 32.01R-VALUE				32a 40a
WINDOWS				EXPOSED FLOORS				
ID 1: 1/ (Windows (Energy Modelling Requirements)) custom, USI: 1.3, SHGC: 0.25				ID 1: 1/ (TYP. EXPOSED FLOOR), inside floor, // Finished floor w/ underlay, // 3/4" ply, // framing w/ cavity insulation: softwood (default), 2x12 joists @ 16"OC, R35 (9.25") // Exterior finished material. // outside air: 30.98R-VALUE				49a 43a
SKYLIGHTS				DOORS				
ID 1: 1/ (SKYLIGHT) double glazed, Fixed — Wood/Vinyl, insulating, low-E, 13mm Air, USI: 1.96, SHGC: 0.47				ID 1: 1/ (EXT. DOOR) Insulated metal — Polyurethane core, without storm door, USI: 0.91				52a 46a
FOUNDATIONS								
ID 1: 1/ [Heated Crawlpace] Concrete Slab & Walls, insulation: below slab = 2.64RSI, interior wall = 2.11RSI, exterior wall = 2.11RSI (configuration #69) // any first storey construction type, interior surface of wall insulated over full-height, exterior surface of wall insulated over full-height, sub-surface of floor slab fully insulated but no insulation								53a
Issued: August 22, 2025						67 Page: 2-2 of 3		
 TECA HEAT LOSS & HEAT GAIN CALCULATOR				 HVAC DESIGNERS OF CANADA VERIFIED F280 SOFTWARE				

CSA F280-12 INPUT SUMMARY					CSA F280-12 Form Set Ver 24.10	
These documents issued for the use of <u>BC MINISTRY OF HOUSING</u> 1 and may not be used by any other persons without authorization. Documents for permit and/or construction are signed in red.					PROJECT #: <u>TOWN1-U4-SOUTH</u> 2	
Model: <u>TOWN-01-UNIT 4</u>		3	Site: <u>SOUTH</u>		6	
Address:		4	Lot:		7	
City & Province: <u>PRINCE GEORGE, BC</u>		5	Postal Code:		8	
CALCULATION RESULTS - ROOM BY ROOM (BTUH)						
#	ROOM NAME	71	HEATING	72	TOTAL COOLING	73
1	(#1)HEATED CRAWL - U4		5,261		36	
2	(#2)112-ENTRY		1,849		381	
3	(#3)113-POWDER ROOM		200		22	
4	(#4)114-LIVING ROOM		2,090		3,611	
5	(#5)115-KITCHEN/DINING		5,288		5,001	
6	(#6)212-LANDING		1,645		399	
8	(#8)214-BEDROOM 1		2,411		816	
9	(#9)215-BEDROOM 2		2,411		1,168	
10	(#10)305-LANDING		2,360		1,481	
11	(#11)306-WASHROOM		141		63	
12	(#12)307-BEDROOM 3		2,094		589	
13	(#13)308-BEDROOM 4		2,088		936	
Ventilation Loss (if separate):		2,739	BTUH	74	Latent Gain (if separate, value or multiplier):	3,347 BTUH 75
Total Building Heat Loss (5.2.7):		27,840	BTUH	Nominal Cooling System Capacity (6.3.1):		14,504 BTUH
See page 1 for heating & Cooling System Capacity Limits				Issued: August 22, 2025	76	Page: 3 of 3
			TECA HEAT LOSS & HEAT GAIN CALCULATOR		 HVAC DESIGNERS OF CANADA VERIFIED F280 SOFTWARE	